



# West Valley Demonstration Project

West Valley  
Environmental  
Services

## Permeable Treatment Wall Project

**John Chamberlain**


May 26, 2010

West Valley Citizen Task Force Meeting

20614\_1



# West Valley Demonstration Project




20614\_2



WVES LLC

# Valley Cross Section



On the North Plateau, 10–30 feet of relatively permeable material occurs above a confining (low permeability) clay layer

Precipitation that infiltrates in this area moves downward to the clay layer and then downgradient to the northeast

The groundwater surfaces at the edge of the plateau as seeps or springs

GENERALIZED EAST-WEST GEOLOGIC CROSS SECTION AT THE WEST VALLEY DEMONSTRATION PROJECT


NOTE:  
Vertical scale = 1/4 horizontal scale.  
Adapted from Dana et al. (1979a).



WVES LLC


# Background – Groundwater Plume

- ◆ In late 1993, contaminated groundwater surfaced in ditches on the North Plateau
- ◆ Geoprobe® investigation (small diameter wells) was conducted in the summer of 1994 to determine nature and extent of contamination
- ◆ Contaminant involved is Strontium-90 (Sr-90) and has been attributed to a process line(s) leak(s) during reprocessing in the 1970s



Area of leading edge of Sr-90 plume

## Background - Groundwater Plume



20614\_5

## Background – Groundwater Plume

- ◆ Pump and treat system installed in the fall of 1995 to mitigate surfacing and off-site movement of contaminated groundwater
- ◆ Between 1996 and 1998 surface water drainage changes made north of the Main Plant
- ◆ Pilot PTW installed in 1999
- ◆ Detailed evaluation of the pilot PTW completed in 2002





FIGURE 4.5  
 Sr-90 Groundwater Plume on the North Plateau

— pumping wells location  
 — pilot PTW location

20614\_6





West Valley Demonstration Project  
**Alternatives Evaluated**  
 WVES LLC

Alternative 1	Maintain Current Approach
Alternative 2	Interceptor Trench Drain
Alternative 3	Groundwater Extraction Wells
Alternative 4	Far Downgradient Interceptor Trench Drain
Alternative 5	Far Downgradient Groundwater Extraction Wells
Alternative 6	In-situ Plume Treatment with Passive PTW
Alternative 6A	In-situ Plume Treatment with Active PTW
Alternative 7	Far Downgradient In-situ Plume Treatment with Passive PTW

Leading edge of Sr-90 plume

Far Downgradient


20614\_8





# Hydrogeologic Cross-Section

Along PTW Alignment




20614\_11



# Laboratory Testing of Zeolites

- ◆ Two natural zeolites high in clinoptilolite content are being tested through the University at Buffalo (UB)
  - Grain size analysis
  - Permeability mineral composition
  - Cation exchange capacity
  - West Valley strontium specific removal (column tests)
    - Non-radioactive columns (at UB) using simulated groundwater; Sr-88 surrogate for SR-90, 5 key cations (Na, Ca, K, Mg, Sr)
    - Radioactive columns (at WVDP) using actual North Plateau groundwater (~50,000 pCi/L)



Non-radioactive column tests

20614\_12



# Bear River Zeolite - Idaho



Exposed section of zeolite



Bear River Mine

Truck being loaded with one ton bags of zeolite (20 bags /truck)



20614\_13



# PTW Location



**PTW Dimensions**  
~800 feet long  
~3 feet wide  
18-30 feet deep

20614\_14



## PTW Installation

- ◆ PTW installation is planned to be done with a continuous, one-pass trencher that cuts a trench and fills with media (zeolite) in one operation
  - Trencher allows installation of PTW without use of support piles or in-trench slurry avoiding possible impacts to permeability at soil-zeolite interface

Note: Trencher limited to approximately 30 foot excavation with 3-foot wide trench



*Trencher equipped with 25' bar, 2' wide cutter*

20614\_15




## Concept to Design to Installation

- ◆ Following have been established
  - PTW location
  - Media (zeolite) to use
  - Installation approach (one-pass trencher)
- ◆ Focus now on installation (construction)
  - Equipment access, operation, decontamination
  - Soil management
  - Surface water drainage
  - Contingencies

20614\_16




# Alignment Borings



20614\_17



# PTW Installation



20614\_18



# PTW Installation

WVES LLC




20614\_19



# PTW Installation

WVES LLC



20614\_20



## PTW Installation

- ◆ Projections (approximate)
  - 800-feet long, 3-feet wide, 18-30-feet deep
  - 75,000 cubic feet of soil excavated
  - 2,000 metric tons of zeolite



## Status as of May 26, 2010

- ◆ Formal design done
- ◆ First shipment of zeolite received in May with shipments planned through mid-summer
- ◆ Work focused on requests for proposals for trencher and general contractor
- ◆ Site preparation targeted to begin in mid- to late summer
- ◆ PTW installation (trenching) fall 2010